

Addendum #2 – April 6, 2020
Contract WR20-002
2019 Water Utility Capital Works

1) **Question:** Will further anodes be required at the wet tap location as well as an isolation kit?

Answer: The 14.5kg anode at the tie-in is to be linked to all fittings including the wet tap. The contractor may install 2 x 7.7kg anodes instead. An isolation kit is required as well.

END